


**CAUTION**

**This is a generic diagram only and must be reviewed and modified if necessary, for each specific site. Evidence of review and modifications must be recorded on appropriate documentation.**

**ALL SIGNAGE BELOW TO BE INSTALLED ON BOTH APPROACHES TO THE WORK ZONE**



**TRAFFIC CONTROL  
DIAGRAM**

CLEARANCE FROM TRAFFIC LANE TO  
WORKERS AND VEHICLES  
IS BETWEEN 1.2m AND 3.0m  
- 70, 80 OR 90KM/HR -

**PROJECT MANAGEMENT:**

**Client:** Department of  
Environment and  
Conservation  
**Contact:** Refer Bottom of  
Risk Analysis  
**After Hours Contact:** District Duty  
Officer - Local DEC  
**Project Duration:** To be Advised  
**Commencement Of  
Works:** To be Advised  
**Classification Of  
Works:** Prescribed Burning

**PROJECT SPECIFICATIONS:**

**Notes:**

1. Leave a 1.2 metre clearance between the worksite and the flow of traffic.
2. Ensure that any existing permanent signage within the extent of the site is covered whilst works are in progress. Remove cover on completion of the works, inclusive of "U-Turn" signage.
3. Remove "Symbolic Worker" sign when workers are not visible or on site and replace with "Smoke Hazard" sign.
4. A distance of 500m between signs is required when repeater speed signage is used.

**SIGNAGE SPACING:**

"D" (metres), for the positioning of signs, is related to the speed of traffic as follows

**VALUE OF DIMENSION D**

Speed of traffic km/h	Dimension D m
45 or less	10
46-55	15
56 - 65	45
Greater than 65	Equal to speed of traffic, in km/h

**SIGNS SCHEDULE:**

Sign	Quantity	Sign No.
Symbolic Worker	4	T1-5
End Road Work	2	T2-16
Speed Restrictions	6	R4-1B
Reduce Speed	2	G9-9A
End Speed Restrictions	2	R4-12B
Smoke Hazard	2	T4-6B

For full supporting details refer to Traffic Management Plan Document. This plan is suitable to use for this work site and date only. Any unauthorised use or reproduction in full or part is forbidden.



OPUS INTERNATIONAL CONSULTANTS (PCA) LIMITED  
23 SPENCER STREET, BUNBURY, WESTERN AUSTRALIA 6230  
PO BOX 421, BUNBURY, WESTERN AUSTRALIA 6230  
TEL: 08 97923000 FAX: 08 97923030

WEBSITE: [www.opus.com.au](http://www.opus.com.au)

**DRAWING No:** DEC/003

**DESIGNER:** Brad Brooksby

**CERT No:** K33946

**SIGNED:**

**REV. No:** 04 **DATE:** 14/9/2010