


CAUTION

This is a generic diagram only and must be reviewed and modified if necessary, for each specific site. Evidence of review and modifications must be recorded on appropriate documentation.

NOTE:
T2-16 SIGNAGE TO BE USED WHEN
BURNING OFF DURATION IS LONGER
THAN ONE DAY.



TRAFFIC CONTROL DIAGRAM

DUAL CARRIAGEWAY
70; 80 & 90km/hr SPEED ZONES
REDUCED TO ONE LANE

PROJECT MANAGEMENT:

Client: Department of Environment and Conservation
Contact: Refer Bottom of Risk Analysis
After Hours Contact: District Duty Officer - Local DEC
Project Duration: To be Advised
Commencement Of Works: To be Advised
Classification Of Works: Prescribed Burning

PROJECT SPECIFICATIONS:

Notes:

1. Leave a 1.2 metre clearance between the worksite and the flow of traffic.
2. Ensure that any existing permanent signage within the extent of the site is covered whilst works are in progress. Remove cover on completion of the works
3. A distance of 500m between signs is required when repeater signage is used.
4. Remove "Worker Symbolic" sign and replace with "Smoke Hazard" sign when workers are not visible or on site.

SIGNAGE SPACING:

"D" (metres), for the positioning of signs, is related to the speed of traffic as follows

VALUE OF DIMENSION D

Speed of traffic km/h	Dimension D m
45 or less	10
46-55	15
56 - 65	45
Greater than 65	Equal to speed of traffic, in km/h

SIGNS SCHEDULE

Sign	Quantity	Sign No.
Symbolic Worker	T1-5	2
End Road Work	T2-16	2
Smoke Hazard	T4-6B	2
Speed Restriction	R4-1B	2
Speed Reinstatement	R4-1B	2
Reduce Speed	G9-9A	2
Lane Status Sign	T2-6-1	4
Temporary Hazard Marker	T5-5	1
Temporary Hazard Marker	T5-4	2
Variable Message Board	▲	1
Legs		38

For full supporting details refer to Traffic Management Plan Document. This plan is suitable to use for this work site and date only. Any unauthorised use or reproduction in full or part is forbidden.



OPUS INTERNATIONAL CONSULTANTS (PCA) LIMITED
23 SPENCER STREET, BUNBURY, WESTERN AUSTRALIA 6230
PO BOX 421, BUNBURY, WESTERN AUSTRALIA 6230
TEL: 08 97923000 FAX: 08 97923030

WEBSITE: www.opus.com.au

DRAWING No: DEC/013

DESIGNER: Brad Brooksby

CERT No: K33946

SIGNED:

Brad Brooksby

REV. No: 04

DATE: 14/9/2010